



Engineering cell
Delhi Technological University
Shahbad Daulatpur, Bawana Road, Delhi-110042

File No: DTU/Engg.Cell/003425/2022-23/Electrical/

Dated: 26-10-2022

NOTICE INVITING QUOTATION

The Chief Project Officer, Engineering Cell DTU invites, on behalf of Delhi Technological University, sealed percentage rate short terms quotations from Electrical Contractors up to 3:00 PM on 01/11/2022 for the following works, which shall be opened at 3:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer on all working days by submitting an application along with a copy of G.S.T. No. and PAN Card up to 03:00 P.M. on 01/11/2022.

S. No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Supply and drawing of control cable for Generator in East Delhi Campus, Vivek Vihar Phase II, Jhilmil Colony, DTU.	4, 18,186/-	10 days	01-11-2022

TERMS & CONDITIONS:-

1. The work shall be carried out as per CPWD specifications/manufacturer's specification.
2. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
3. No T&P shall be issued to the firm by the department.
4. All necessary recoveries shall be recovered from the bill.

Enclosure: Schedule of work.

Anwar
26/10/22
Chief Project Officer
DTU Campus, Bawana Road
Delhi

Copy to:-

1. Sr. Account Officer, DTU
2. DTU Website
3. Guard File

B
26.10.22
Project Officer Electrical
DTU Campus, Bawana Road
Delhi

Schedule of work

Name of Work: Supply and drawing of control cable for Generator in East Delhi Campus, Vivek Vihar Phase II, Jhilmil Colony, DTU.


Sl.No	Description of Work / Item(s)	Qty	Units	Rate	Amount
1	Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc. as required. DSR-7.1.4				
a	Above 185 sq. mm and upto 400 sq. mm	150	mtrs		
2	Supplying, and laying 1.1 KV grade PVC insulated PVC sheathed copper unarmoured cables for controlling the AMF panel and DG set system dressing, saddling, cable gland etc.				
a	12 core, 2.5 sq,mm Cu. Cable	50	mtrs		
3	Supplying of one number PVC insulate d and PVC sheathed / XLPE power cable of 1.1 KV grade etc as required.				
a	3.5 x 240 sqmm	150	Meter		
				Total	



Chief Project Officer (DTU)



Project Officer Electrical


26/10/2022
Junior Engineer (E)