



**Engineering Cell**  
**Delhi Technological University**  
Shahbad Daulatpur, Bawana Road, Delhi-110042

Dated: 20.08.2025

File No: DTU/Engg.Cell/0055/2025-26/Civil

**NOTICE INVITING QUOTATION**

The Chief Project Officer, Engineering Cell DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Civil Contractors/Suppliers up to 03.00 PM on 27.08.2025 for the following works, which shall be opened at 03:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer on all working days by submitting an application along with a copy of G.S.T. No. or PAN Card up to 02:00 PM on 27.08.2025.

S.No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Special repair and renovation work in Room's balcony area in CVR hostel at DTU campus.	4,95,962/-	30 days	27.08.2025

**TERMS & CONDITIONS:-**

1. The work shall be carried out as per CPWD specifications and as per direction of Engineer-in-Charge.
2. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
3. The quotations which are issued from the office of CPO shall only be accepted, quotations in other forms shall be summarily rejected without assigning any reasons.
4. No T&P shall be issued to the firm by the department.
5. Necessary recoveries shall be made from the bill.
6. Penalty on account of delay of the work due to any reason (if any) may be imposed @500/- per day or as decided by the Engineer-in-Charge.
7. Any damages/ unforeseen charges during the work shall be borne by contractor. Nothing shall be paid in this account.
8. Water Charges @1% and Electricity Charges @1% shall be deducted from the bill.
9. **Contractor should have work experience for building repairing works. Copy of relevant document i.e. work completion certificate/ work order should be submitted along with the NIQ. (Single work executed of 80% or two work of 60% or three work of 40% of Estimated Cost during last 7 years of last date of receipt of NIQ).**
10. All materials should be as per the approved make as decided by the Engineer-in-Charge. Contractor should submit the samples for approval before executing the work.
11. The lowest contractor will be required to furnish/ submit performance guarantee (P.G.) of 5% (Five Percent) of the quoted value of the work amount within 03 working days from the date of issue of P.G. letter. Thereafter, the work will be awarded and P.G. will be released only after successfully completion of work. In case of non-performance, the same shall be forfeited.

**Enclosure: Schedule of work & Approved make list.**

20/8/2025  
Executive Engineer

Copy to: -

1. Registrar, DTU
2. Sr. Account Officer, DTU
3. A.E.(Civil)/J.E. (Civil)
4. DTU Website
5. Notice Board

20/8/25  
A.E. (Civil)



### **APPROVED MAKES OF MATERIALS (CIVIL)**

The Contractor shall obtain prior approval from the Engineer-in-charge before placing order for any specific material or engaging any of the specialized agencies. The Contractor shall make a detailed submission with catalogues and proposed specifications, as well as full details of the works executed by the specialized agency, as specified. Unless otherwise specified, the brands/makes of the material as specified in the item nomenclature, in the list of approved materials attached in the tender and in the particular specifications shall be used in the work. In case of non-availability of the brands specified in the contract the Contractor may be allowed to use alternate equivalent brand of the material by Engineer-in-Charge with the prior approval of NIT Approving Authority subject to submission of documentary evidence of non - availability of the specified brands by contractor. The necessary cost adjustments on account of above change shall be made for the same. The contractor would submit copy of original bills and manufacturer's test certificate for all lots of material procured for the work, payments would be released only for the items for which original bills & manufacturer's test report for the material consumed has been submitted to Engineer-in-Charge. Department shall also get random testing of material from testing Laboratory of its choice.

### **LIST OF APPROVED MAKES OF MATERIALS [CIVIL WORK]**

S.NO.	MATERIAL	MANUFACTURERS NAME
1.	CEMENT	ACC, ULTRATECH, AMBUJA, J.K., LAFARGE, BIRLA, CCI, J.K. SUPER CEMENT
2.	REINFORCEMENT STEEL-TMT BARS-FE-500D GRADE	SAIL, TATA STEEL, RINL, JSW, JSPL
3.	STRUCTURAL STEEL SECTIONS	SAIL, TISCO, RINL, JSW, JINDAL STEEL & POWER, TATA, APPOLO
4.	STRUCTURAL STEEL TUBES/PIPES	JINDAL, TATA, APL APOLLO, LLOYDS, SAIL, TATA, JSW
5.	LGSF VENDORS	M/S INTERARCH BUILDING PRODUCTS PVT. LTD., M/S TATA BLUESCOPE STEEL LTD., M/S MGI INDIA PVT. LTD., M/S JSPL, M/S EVEREST INDUSTRIES LTD., M/S WOOTZ BUILDSYS LLP., M/S EPACK POLYMERS.
6.	READY MIXED CEMENT CONCRETE	ACC, LAFARGE, ULTRATECH, SHREE, ALCHON, L&T GRASIM, NSCONCRETE, RMC READYMIX (INDIA), SHAILA ENTERPRISES, RDC CONCRETE, TECHNO PRIME RMC PVT LTD, VK READY MIX CONCRETE, ASHTECH, SHRI RAM READY MIX CONCRETE
7.	ANTI-TERMITE TREATMENT AGENCY	PEST CONTROL INDIA LTD, GODREJ PEST CONTROL, CAPITAL PEST CONTROL (INDIA)
8.	CHEMICAL TO BE USED FOR 20% E.C.ANTI- TERMITE TREATMENT	DE-NOCIL AND BAYER
9.	SHUTTERING PLY	GREENPLY SHUTTERING PLY, ARCHID SHUTTERING PLY, EURO SHUTTERING PLY
10.	SUPERPLASTICIZERS	MC BAUCHEMIE/FOSROC/SIKA/BASF/CHRYSO/VELOSIT/PIDILITE
11.	WHITE CEMENT	BIRLA WHITE , J.K. WHITE
12.	AAC BLOCK	SHREE, INSTABLOCK, BILTECH, MAGICRETE, SIPROX, BIRLA AEROCON, J.K., CLAVECON INDIA PVT. LTD., J.K. LAKSHMI, B.G. SHIRKE/ INDO BHUTANCONSTRUCTION SOLUTION, ULTRATECH XTRALITE,



13.	BLOCK JOINTING MORTAR	JK LAKSHMI, BIRLA AEROCON SMARTFIX, MYK SCHOMBURG, ULTRATECH, FERROUSCRETE, ARDEX
14.	GLAZED CERAMIC TILES	RAK CERAMICS, SOMANY, KAJARIA, ORIENT BELL
15.	VITRIFIED TILES	RAK CERAMICS, SOMANY, KAJARIA, ORIENT BELL
16.	WALL PUTTY	JK WHITE, BIRLA WHITE, ASIAN, BERGER, BIRLA, JSW
17.	PLASTER OF PARIS	JK LAKSHMI, SAKARNI, SHRIRAM, NIRMAN
18.	GYPSUM PLASTER	SAINT GOBAIN, SAKARNI, J.K. LAKSHMI
19.	ANCHOR PLUG SOIL/ ROCK ANCHOR	BBR, VSL, FREYSSINET
20.	PORCELAIN TILES	JOHNSON, ASIAN(AGL)
21.	CHEQUERED TILE	NITCO, ULTRA, UNISTNOE, MODERN
22.	CC PAVERS, PRECAST CC KERB STONE, CC TILES, RCC SLAB	NITCO, BHARAT, HINDUSTAN, ULTRA, KJS CONCRETE, DURACRETE, KK MANHOLE & COVERS, TERRA FIRMA, PAVER INDIA, DALAL, UNISTONE, CECO, S&S, MOON LIGHT, SWASTIK, ECOCRETE
23.	GRASS PAVER	UNISTONE, ULTRA, HINDUSTAN, KK, KJS
24.	SFRC/PRECAST C.C. COVERS	KK MANHOLE & COVERS, JAIN, PRAGATI, HINDUSTAN
25.	FLYASH BRICKS	POWER BRICK, YBW PROJECT, ASHTECH INDUSTRIES PVT. LTD.
26.	GLASS MOSAIC TILES	PALLADIO, CORAL, MRIDUL, BISAZZA, MMG TILES
27.	INSULATION FOR PIPE, RUBBER INSULATION	KAIFLEX, ARMAFLEX, CAREFLEX, VIDEOFLEX AFLEX
28.	COPPER TUBES/ PIPES	RAJCO, MEXFLOW, DELHI METAL, ABC
29.	READY MIX PLASTER	BIRLA AEROCON, ULTRATECH, RAMCO, WEBER, LATICRETE
30.	RAISED / CAVITY FLOORING	UNI FLOOR, UNITILE INDIA, TATE, ZTFLOOR, ACCESS FLOOR SYSTEMS
31.	DECK SHEET	JSW, TATA BLUESCOPE, INTERARCH, JSPL, ROOFCLAD
32.	SELF-DRILLING SCREWS	TW BUILDEX & BOUSTED, CORROSHIELD, ATUL FATHERNERS LTD.
33.	CPVC PIPE AND FITTINGS	PRINCE, SUPEREME, ASTRAL
34.	LABORTORY SINK	CERA, HINDWARE, JAQUARE
	PAINTS	
1.	WATER-PROOFING CEMENT PAINT	ASIAN, BERGER, DULUX
2.	ACRYLIC EXTERIOR PAINT	ASIAN (APEX ULTIMA ), BERGER (WEATHER COAT LONGLIFE), DULUX (WEATHER SHIELD POWER FLEX)
3.	SYNTHETIC ENAMEL PAINT	ASIAN (APCOLITE), BERGER (LUXOL GLOSS), DULUX (DULUX GLOSS)



4.	PLASTIC/ACRYLIC EMULSION PAINT	ASIAN (ROYAL SHYAN), BERGER (SILK GALMOUR), DULUX (VELVET TOUCH DIAMOND)
5.	ACRYLIC DISTEMPER	ASIAN (AQUA LOCK ACRYLIC), BERGER (Bison SUPER), DULUX (MAGIC ACRLYIC)
6.	CEMENT PRIMER	ASIAN (DECOPRIME), BERGER (SOLVENT BASE), DULUX (SOLVENT BASE)
7.	WALL PUTTY	BIRLA, J.K., JSW
	SPORTS WORK	
1.	WOODEN FLOORING	ASIAN, YONEX, ACTION FLOOR SYSTEM, APEX SPORTS FLOORING
	Others	
1.	ALUMINIUM SECTIONS AND FITTINGS	JINDAL ALUMINIUM, NALCO, HINDALCO INDUSTRIES, FINESTA, BHARAT ALUMINIUM COMPANY
2.	FLOAT GLASS	SAINT GOBIN, MODI GUARD
3.	PARTICLE BOARD	ACTION TESA, CENTURYPLY, GREENPLY, MERINO, ARCHIDPLY DECOR
4.	ROLLER BLINDS	VISTA, MAC
5.	BLOCK BOARD	CENTURY PLY, GREENLAM, ACTION TESA, KIT PLY
6.	LAMINATED SHEET	MERINO, GREENLAM, CENTURY PLY
7.	S.S. FITTINGS FOR WOODEN WORK	HARDWYN, GODREJ, HETTICH
8.	G.I. SHEET	SAIL, TATA, JINDAL, ISPAT, JSW, JSPL

The Agency is required to get prior approval of Engineer-in-charge for the make of the material to be used in the work. In case of non-availability of material from these manufacturers, the Hon'ble Vice Chancellor, DTU may allow use of alternative BIS approved manufacturer makes.

Chief Project Officer  
Delhi Technological University

int (Rs.)

,924.00

70.58

7.04



# Schedule of work

Name of Work:- Special repair and renovation work in Room's balcony area in CVR hostel at DTU campus.


S.No.	DSR 2021 Code	Item description	UoM	Qty	Rate (Rs.)	Amount (Rs.)
1	18.76.1	Cutting holes up to 30x30 cm in walls including making good the same: With common burnt clay F.P.S. (non modular) bricks	Each	135.00	362.40	48,924.00
2	4.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
2.1	4.1.8	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum	31.50	6326.05	1,99,270.58
2.2	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	Cum	5.25	7365.15	38,667.04
3	14.72	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding. Note: - This item to be used for maintenance work judicially, necessary deduction for scaffolding in the existing item to be done.	Sqm	325.00	285.00	92,625.00
4	12.41.2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 110 mm diameter	Mtr	67.00	319.75	21,423.25
5	14.75	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	Sqm	34.00	540.35	18,371.90




21c

6	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	Cum	50.00	219.35	10,967.50
7	13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade : New work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	Sqm	34.00	166.85	5,672.90
					<b>Total=</b>	<b>4,35,922.16</b>
		Add GST Multiplication factor (0.0633) of 18% in place of 12%=				27,593.87
					<b>Total=</b>	<b>4,63,516.04</b>
		Add Cost Index on DSR 2021 Items @7%=				32,446.12
					<b>Total Rs.=</b>	<b>4,95,962.00</b>

  
J.E (Civil)

  
A.E (Civil) 26/5/25

  
E.E./ CPO, DTU 30/5/25