



DELHI TECHNOLOGICAL UNIVERSITY
Shahbad Daulatpur, Bawana Road, Delhi – 110042
Email Id:- cpo@dtu.ac.in Tel: 011-27852188

F.NO: DTU/E.C./0062/2024-25/Electrical

Dated: 31/07/2024

NOTICE INVITING QUOTATION

The Chief Project Officer, Engineering Cell, DTU invites, on behalf of Delhi Technological University, sealed item rate Notice Inviting Quotations from specialised agencies for electrical works up to 05.08.2024, 3:00 PM which shall be opened at 3:00 PM on the same day. N.I.Q./Schedule of work along with terms and conditions can be obtained from office of the Engineering Cell on all working days by submitting an application along with Similar Works, Electrical Licence and G.S.T. Registration certificate. The NIO/Schedule of work can also be taken from DTU website i.e. www.dtu.ac.in

S. No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last Date of Receipt of Quotation
1.	Repair, maintenance and servicing for high-tension (HT) electrical panel's incoming 11KV feeders, DTU Delhi	Rs.3,68,850/-	07 Days	05.08.2024 till 03:00 PM

Terms & Conditions: -

- Before tendering/quotationing, the Bidder shall visit the site and satisfy himself as to the site conditions, the accessibility of the site of full extent and implication of the operation, the nature of the ground and working conditions affecting labour and execution of the work. No claim on these issues will be entertained.
- The contractor shall have to get the site of work cleared during execution and/ or on completion of work as per directions and to the satisfaction of client.
- The rate quoted should be inclusive of all the taxes and duties, GST etc. & nothing extra shall be paid on any account.
- The quotation which are issued from the office of CPO shall only be accepted, quotations in any other forms shall be summarily rejected without assigning any reasons.
- No T&P shall be issued to the firm by the department for installation at site.
- All necessary recoveries shall be made from the bill.

Encls. Schedule of work.

Anwar
31/7/24
Chief Project Officer

Copy to:-

1. Notice Board/Website
2. Guard File.


31.07.24
Project Officer (Elect.)

Schedule of Work

Name of work:- Repair, maintenance and servicing for high-tension (HT) electrical panel's incoming 11KV feeders, DTU Delhi

S.No.	Item Description	Qty	Unit	Rate Rs	Amount Rs.
1	Repairing and Servicing of Draw out type 11 KV, 630 Amp, 3 phase, 50 Hz VCB, from the HIT panel complete cleaning of male and female contacts tightening the connection checking of wiring system, replacement of minor spare parts such as spring, nuts bolt & washer, setting right the mechanism and reassembling, testing and commissioning etc as reqd.	7	Job		
2	Servicing, Checking of over load & earth fault relay, cleaning. Checking of wiring system calibration with secondary injection test kit, setting of tripping according to the load complete with testing and commissioning as reqd.	7	Job		
3	Annual maintenance of HT Panel board main bus bar and outgoing CT, Insulator, bus bar, HT connection i/c testing & dismantling the existing Panel board nut bolt, washer etc complete as reqd.	7	Job		
4	Supplying & Fixing the Automatic space heater 240 Volt AC in the existing 11 KV HT panel of VCB. i/c testing control wiring & dismantling the existing defective space heater etc complete as reqd.	10	Job		
5	Supply and making 11 KV end termination box size 300*3 Sq MM complete lages, sleeve etc as required.	2	Job		
6	Fault locating charges for 11 KV HT cable size 300 * 3 SQ MM found the fault pin point exjct location etc as required.	2	Job		
7	Supplying & replacement of the defective accessorise of LT panel i/c dismantling defective accessorise assembling the existing unit etc as reqd.				
a	Power pack unit input supply 220 & out put supply 24 Volt DC.	1	No.		
b	Supply of contractor, Contactor coil voltage 220 volt AC, with 2 NO + 2 NC contact	3	Nos.		
c	UVR, OVR, Monitoring & Protection	3	Nos.		
d	UVR 415 Volt AC	7	Nos.		
e	UPS 2 KVA	1	No.		
f	On delay timer 220 Volt AC	2	Nos.		
g	Shuntrip relay	3	Nos.		
Total					
Say's Rs.					

Terms and conditions: -

1. The work shall be carried out as per entire satisfaction of the Engineer in charge.
2. Quoted rates shall be inclusive of all taxes applicable and cartage etc.
3. No T & P shall be issued to the contractor by the department.
4. All safety measure shall be taken while execution of work.
5. Time period for completion of work is 07 days.



JE (Elect.)



Project Officer (Elect.)



Chief Project Officer