



Engineering Cell
Delhi Technological University
Shahbad Daulatpur, Bawana Road, Delhi-110042

File No: DTU/Engg.Cell/00184/2025-26/Civil

Dated: 14.07.2025

NOTICE INVITING QUOTATION


The Chief Project Officer, Engineering Cell DTU invites, on behalf of Delhi Technological University, sealed percentage rate quotations from Civil Contractors/Suppliers up to 03.00 PM on 18.07.2025 for the following works, which shall be opened at 03:30 PM on the same day. Schedule of work along with terms and conditions can be obtained from office of the Chief Project Officer on all working days by submitting an application along with a copy of G.S.T. No. or PAN Card up to 02:00 PM on 18.07.2025.

S.No.	Name of Work	Estimated Cost (Rs.)	Time Allowed	Last date of Receipt of Quotation
1.	Providing and fixing Profile Sheet for Roofing and Kota Stone flooring of Team Defianz Racing Lab premises in Wind Tunnel Lab at DTU campus.	4,74,427/-	20 days	18.07.2025

TERMS & CONDITIONS: -

1. The work shall be carried out as per CPWD specifications and as per direction of Engineer-in-Charge.
2. The rates quoted should be inclusive of all the taxes and duties & nothing extra shall be paid.
3. The quotations which are issued from the office of CPO shall only be accepted, quotations in other forms shall be summarily rejected without assigning any reasons.
4. No T&P shall be issued to the firm by the department.
5. Necessary recoveries shall be made from the bill.
6. Penalty on account of delay of the work due to any reason (if any) may be imposed @500/- per day or as decided by the Engineer-in-Charge.
7. Any damages/ unforeseen charges during the work shall be borne by contractor. Nothing shall be paid in this account.
8. Water Charges @1% and Electricity Charges @1% shall be deducted from the bill.
9. **Contractor should have work experience for building repairing works. Copy of relevant document i.e. work completion certificate should be submitted along with the NIQ. (Single work of 80% of Estimated Cost).**
10. All materials should be as per the approved make as decided by the Engineer-in-Charge. Contractor should submit the samples for approval before executing the work.

Enclosure: Schedule of work & Approved Make List.


14/7/25
Executive Engineer

Copy to:-

1. Registrar, DTU
2. COF, DTU
3. Sr. Account Officer, DTU
4. A.E. (Civil)/ J.E. (Civil)
5. Notice Board


14/7/25
A.E. (Civil)

APPROVED MAKES OF MATERIALS (CIVIL)

The Contractor shall obtain prior approval from the Engineer-in-charge before placing order for any specific material or engaging any of the specialized agencies. The Contractor shall make a detailed submission with catalogues and proposed specifications, as well as full details of the works executed by the specialized agency, as specified. Unless otherwise specified, the brands/makes of the material as specified in the item nomenclature, in the list of approved materials attached in the tender and in the particular specifications shall be used in the work. In case of non-availability of the brands specified in the contract the Contractor may be allowed to use alternate equivalent brand of the material by Engineer-in-Charge with the prior approval of NIT Approving Authority subject to submission of documentary evidence of non - availability of the specified brands by contractor. The necessary cost adjustments on account of above change shall be made for the same. The contractor would submit copy of original bills and manufacturer's test certificate for all lots of material procured for the work, payments would be released only for the items for which original bills & manufacturer's test report for the material consumed has been submitted to Engineer-in-Charge. Department shall also get random testing of material from testing Laboratory of its choice.

LIST OF APPROVED MAKES OF MATERIALS [CIVIL WORK]

S.NO.	MATERIAL	MANUFACTURERS NAME
1.	CEMENT	ACC, ULTRATECH, AMBUJA, J.K., LAFARGE, BIRLA, CCI, J.K. SUPER CEMENT
2.	REINFORCEMENT STEEL-TMT BARS-FE-500D GRADE	SAIL, TATA STEEL, RINL, JSW, JSPL
3.	STRUCTURAL STEEL SECTIONS	SAIL, TISCO, RINL, JSW, JINDAL STEEL & POWER, TATA, APPOLO
4.	STRUCTURAL STEEL TUBES/PIPES	JINDAL, TATA, APL APOLLO, LLOYDS, SAIL, TATA, JSW
5.	LGSF VENDORS	M/S INTERARCH BUILDING PRODUCTS PVT. LTD., M/S TATA BLUESCOPE STEEL LTD., M/S MGI INDIA PVT. LTD., M/S JSPL, M/S EVEREST INDUSTRIES LTD., M/S WOOTZ BUILDSYS LLP., M/S EPACK POLYMERS.
6.	READY MIXED CEMENT CONCRETE	ACC, LAFARGE, ULTRATECH, SHREE, ALCHON, L&T GRASIM, NSCONCRETE, RMC READYMIX (INDIA), SHAILA ENTERPRISES, RDC CONCRETE, TECHNO PRIME RMC PVT LTD, VK READY MIX CONCRETE, ASHTECH, SHRI RAM READY MIX CONCRETE
7.	ANTI-TERMITE TREATMENT AGENCY	PEST CONTROL INDIA LTD, GODREJ PEST CONTROL, CAPITAL PEST CONTROL (INDIA)
8.	CHEMICAL TO BE USED FOR 20% E.C.ANTI- TERMITE TREATMENT	DE-NOCIL AND BAYER
9.	SHUTTERING PLY	GREENPLY SHUTTERING PLY, ARCHID SHUTTERING PLY, EURO SHUTTERING PLY
10.	SUPERPLASTICIZERS	MC BAUCHEMIE/FOSROC/SIKA/BASF/CHRYSO/VELOSIT/PIDILITE
11.	WHITE CEMENT	BIRLA WHITE , J.K. WHITE

12.	AAC BLOCK	SHREE, INSTABLOCK, BILTECH, MAGICRETE, SIPROX, BIRLA AEROCON, J.K., CLAVECON INDIA PVT. LTD., J.K. LAKSHMI, B.G. SHIRKE/ INDO BHUTANCONSTRUCTION SOLUTION, ULTRATECH XTRALITE,
13.	BLOCK JOINTING MORTAR	JK LAKSHMI, BIRLA AEROCON SMARTFIX, MYK SCHOMBURG, ULTRATECH, FERROUSCRETE, ARDEX
14.	GLAZED CERAMIC TILES	RAK CERAMICS, SOMANY, KAJARIA, ORIENT BELL
15.	VITRIFIED TILES	RAK CERAMICS, SOMANY, KAJARIA, ORIENT BELL
16.	WALL PUTTY	JK WHITE, BIRLA WHITE, ASIAN, BERGER, BIRLA, JSW
17.	PLASTER OF PARIS	JK LAKSHMI, SAKARNI, SHRIRAM, NIRMAN
18.	GYPSUM PLASTER	SAINT GOBAIN, SAKARNI, J.K. LAKSHMI
19.	ANCHOR PLUG SOIL/ ROCK ANCHOR	BBR, VSL, FREYSSINET
20.	PORCELAIN TILES	JOHNSON, ASIAN(AGL)
21.	CHEQUERED TILE	NITCO, ULTRA, UNISTONE, MODERN
22.	CC PAVERS, PRECAST CC KERB STONE, CC TILES, RCC SLAB	NITCO, BHARAT, HINDUSTAN, ULTRA, KJS CONCRETE, DURACRETE, KK MANHOLE & COVERS, TERRA FIRMA, PAVER INDIA, DALAL, UNISTONE, CECO, S&S, MOON LIGHT, SWASTIK, ECOCRETE
23.	GRASS PAVER	UNISTONE, ULTRA, HINDUSTAN, KK, KJS
24.	SFRC/PRECAST C.C. COVERS	KK MANHOLE & COVERS, JAIN, PRAGATI, HINDUSTAN
25.	FLYASH BRICKS	POWER BRICK, YBW PROJECT, ASHTECH INDUSTRIES PVT. LTD.
26.	GLASS MOSAIC TILES	PALLADIO, CORAL, MRIDUL, BISAZZA, MMG TILES
27.	INSULATION FOR PIPE, RUBBER INSULATION	KAIFLEX, ARMAFLEX, CAREFLEX, VIDEOFLEX AFLEX
28.	COPPER TUBES/ PIPES	RAJCO, MEXFLOW, DELHI METAL, ABC
29.	READY MIX PLASTER	BIRLA AEROCON, ULTRATECH, RAMCO, WEBER, LATICRETE
30.	RAISED / CAVITY FLOORING	UNI FLOOR, UNITILE INDIA, TATE, ZTFLOOR, ACCESS FLOOR SYSTEMS
31.	DECK SHEET	JSW, TATA BLUESCOPE, INTERARCH, JSPL, ROOFCLAD
32.	SELF-DRILLING SCREWS	TW BUILDDEX & BOUSTED, CORROSHIELD, ATUL FATHERNERS LTD.
33.	CPVC PIPE AND FITTINGS	PRINCE, SUPEREME, ASTRAL
34.	LABORTORY SINK	CERA, HINDWARE, JAQUARE

	PAINTS	
1.	WATER-PROOFING CEMENT PAINT	ASIAN, BERGER, DULUX
2.	ACRYLIC EXTERIOR PAINT	ASIAN (APEX ULTIMA), BERGER (WEATHER COAT LONGLIFE), DULUX (WEATHER SHIELD POWER FLEX)
3.	SYNTHETIC ENAMEL PAINT	ASIAN (APCOLITE), BERGER (LUXOL GLOSS), DULUX (DULUX GLOSS)
4.	PLASTIC/ACRYLIC EMULSION PAINT	ASIAN (ROYAL SHYAN), BERGER (SILK GALMOUR), DULUX (VELVET TOUCH DIAMOND)
5.	ACRYLIC DISTEMPER	ASIAN (AQUA LOCK ACRYLIC), BERGER (Bison SUPER), DULUX (MAGIC ACRLYIC)
6.	CEMENT PRIMER	ASIAN (DECOPRIME), BERGER (SOLVENT BASE), DULUX (SOLVENT BASE)
7.	WALL PUTTY	BIRLA, J.K., JSW
	SPORTS WORK	
1.	WOODEN FLOORING	ASIAN, YONEX, ACTION FLOOR SYSTEM, APEX SPORTS FLOORING
	Others	
1.	ALUMINIUM SECTIONS AND FITTINGS	JINDAL ALUMINIUM, NALCO, HINDALCO INDUSTRIES, FINESTA, BHARAT ALUMINIUM COMPANY
2.	FLOAT GLASS	SAINT GOBIN, MODI GUARD
3.	PARTICLE BOARD	ACTION TESA, CENTURYPLY, GREENPLY, MERINO, ARCHIDPLY DECOR
4.	ROLLER BLINDS	VISTA, MAC
5.	BLOCK BOARD	CENTURY PLY, GREENLAM, ACTION TESA, KIT PLY
6.	LAMINATED SHEET	MERINO, GREENLAM, CENTURY PLY
7.	S.S. FITTINGS FOR WOODEN WORK	HARDWYN, GODREJ, HETTICH
8.	G.I. SHEET	SAIL, TATA, JINDAL, ISPAT, JSW, JSPL

The Agency is required to get prior approval of Engineer-in-charge for the make of the material to be used in the work. In case of non-availability of material from these manufacturers, the Hon'ble Vice Chancellor, DTU may allow use of alternative BIS approved manufacturer makes.

Rajiv
EE/

Chief Project Officer
Delhi Technological University

SCHEDULE OF WORK

Name of work :- Providing and fixing Profile Sheet for Roofing and kota stone flooring of Team Defianz Racing Lab premises in Wind Tunnel Lab at DTU campus.

S.No.	DSR Code	Description of item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	15.41	Dismantling cement asbestos or other hard board ceiling or partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres lead.	150.00	Sqmtr	46.50	₹ 6,975
2.	12.50	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	150.00	Sqmtr	671.55	₹ 1,00,733
3.	12.51.6	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete : Gutter (600 mm over all girth)	45.00	Mtr	1110.60	₹ 49,977
4.	11.26	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	140.00	Sqm	1706.60	₹ 2,38,924
5.	11.27	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	10.00	Sqm	2038.55	₹ 20,386
					Total	₹ 4,16,994
					Add G.S.T. factor of 6.33% (18% - 12%)	₹ 4,43,390
					Add Cost Index @7%	₹ 31,037.28
					Total	₹ 4,74,427

J.E. (C)

A.E. (Civil)

E.E. DTU